

Formular F3

Obiectiv: IMOBIL CH- CORP LABORATOARE

LISTA cu cantitatile de lucrari pe categorii de lucrari

Obiect: REPARATII CURENTE LABORATOARE

Categorie: 01 LABORATOR 35

						[ron]
Nr.	Capitol lucrari	U/M	Cantitatea	Pretul unitar	Valoare	
Crt.	Simbol			a)materiale		
	Denumire resursa			b)manopera		
	Observatii			c)utilaj		
	Corectii			d)transport		
	Liste Anexe			Total(a+b+c+d)		

1	CMTA27A	02	BUCATA	24.00000		
---	---------	----	--------	----------	--	--

TAIERE CU DISC DE OTEL, TEAVA DE OTEL D. < 2"

TEAVA GAZ

2	RCSG10A	02	M	7.50000		
---	---------	----	---	---------	--	--

DEMONTARE CANALE DE VENTILATIE

3	RPCT29A1	82	MP	24.20000		
---	----------	----	----	----------	--	--

DESFACEREA PLACAJELOR FAIANTA

mese laborator + nise

4	RPCH18G	09	MP	24.20000		
---	---------	----	----	----------	--	--

STRAT SUPORT PENTRU FAIANTA DIN OSB

L: LRC48B -M :7801675 -PLACA OSB

5	RPCM35A	02	MP	18.00000		
---	---------	----	----	----------	--	--

PLACARE CU PLACI DIN PANEL ALB

L: LC05G -0001:8558010 -SURUB MONTAJ AUTOFILETANT 25MM/1000 SUPERRAPID

L: LC27B -M :N-00472 -PANEL FLAT 24MM ALB

6	RPCM14B1	82	MP	24.20000		
---	----------	----	----	----------	--	--

PLACAJE FAIANTA PE MESE SI NISE

L: 10138 -0015:2404535 -PLACI CESAROM GLAZUR SIMP. ALB 100X100X 9 C. 1 S7813

Nr. Crt.	Capitol lucrari	U/M	Cantitatea	Pretul unitar	Valoare
	Simbol			a)materiale	
	Denumire resursa			b)manopera	
	Observatii			c)utilaj	
	Corectii			d)transport	
	Liste Anexe			Total(a+b+c+d)	
7	RPCT10A1 82	MP	228.48000		

PREGATIREA PERETILOR PRIN SLEFUIRE IN VEDEREA ZUGRAVIRII

8	CF08C 02	MP	228.48000		
---	----------	----	-----------	--	--

GLET DE IPSOS CU ADAOS ARACET 2 STR (GIPAC) APLIC MAN PE TENC
INT DRISC SAU SUPR ELEM DE BET

9	RPCR08A 09	MP	228.48000		
---	------------	----	-----------	--	--

VOPSIREA,ZUGRAVELI LAVABILE,VOPSEA PA BAZA DE VINACET,LA INT-
EXT,2 STRATURI,TENCUIELI EXIST.

L: LC68G -M :2525124 -VAR LAVABIL PT INTERIOR

10	6113103	KG	57.00000		
----	---------	----	----------	--	--

AMORSA PENTRU VAR LAVABIL INTERIOR

11	IZA05G1 82	MP	4.00000		
----	------------	----	---------	--	--

VOPSIT ANTICOROZ PE SUPRAF DE BETON TENCUIE CU VOPSEA
EPOXIDICA V 3207

VOPSITORII GLAFURI

12	RPZA05G 99	MP	11.00000		
----	------------	----	----------	--	--

VOPSIT.ANTICOROZ.LA CONFECTII METALICE

L: RIZ2A -0008 6107680 -EMAIL GRI PERCLORVINIL SR4070 NTR 54-75

13	RPCR49B1 82	MP	14.50000		
----	-------------	----	----------	--	--

REVOPSIREA CORPURILOR DE RADIATOARE DE CALORIFER 1 STRAT
PESTE CEA VECHIE CU VOPS.PE BAZA DE ALCHID.*

14	RPCR31B1 82	MP	36.00000		
----	-------------	----	----------	--	--

VOPSITORIE CU EMAIL ALCHIDAL PE TIMPLARIE DE LEMN LA INTERIOR SI
EXT.CU DOUA STRATURI *

baituire

Nr.	Capitol lucrari	U/M	Cantitatea	Pretul unitar	Valoare
Crt.	Simbol			a)materiale	
	Denumire resursa			b)manopera	
	Observatii			c)utilaj	
	Corectii			d)transport	
	Liste Anexe			Total(a+b+c+d)	
15	RPCNL-1	MP		3.36000	

REPARATII SI RECONDITIONARE USA DIN LEMN

16	RCSH21A 02	MP		36.00000	
----	------------	----	--	----------	--

SLEFUIREA SI LACUIREA PANOURILOR SI USILOR DIN LEMN RASIN/FOIOASE/STEJAR

17	RPCK02B1 82	MP		12.00000	
----	-------------	----	--	----------	--

REPARARE FISURI PARDOSEALA

18	RPCK44A 02	MP		58.50000	
----	------------	----	--	----------	--

STRAT SUPORT PT. PARDOSELI CU MORTAR AUTONIVELANT DE 3 - 15 MM

19	RPCK12G 02	MP		58.50000	
----	------------	----	--	----------	--

REPARARE PARD.DIN MAT PLASTICE PE STR.SUP.EXISTENT

L: LC62D -M :S-00132 -CORDON SUDURA PVC					
20	CL20A 02	BUCATA		2.00000	

GRILE DE VENTILATIE DIN PLASA SARMA 0,5X0,4M

L: LC41J -0097-6306236 -GRILA VENTILATIE					
21	RPSC16C1 82	BUCATA		2.00000	

INLOC.COMPL.LAV.FAIAN.PORT.SANIT.SEMIPORT.PE CONS.PE CARAM- BETON CU 2 ROB.SAU BAT.ST.TV.SC. PVC-U

L: 11402 -0001:2440474 -LAVOAR PORTELAN CU SPATAR LSD-400MM ALB C. 1 S1540					
L: 11405 -0005:4202797 -SIFON PT LAVOAR TIP BUTELIE ALAMA 1 1/4" S 9611					
L: 11413 -0014:4201339 -BATERIE AMEST LAVOAR FONTA 1/2" EMAIL JET PERL S8732					
22	RPSD01E1 82	BUCATA		2.00000	

INLOC.ROB.SERV.CU RACORD 1/2 TOL

Nr. Crt.	Capitol lucrari Simbol Denumire resursa Observatii Corectii Liste Anexe	U/M	Cantitatea	Pretul unitar a)materiale b)manopera c)utilaj d)transport Total(a+b+c+d)	Valoare
----------	--	-----	------------	---	---------

23	7730406	BUCATA	1.00000		
----	---------	--------	---------	--	--

INCALZITOR DE APA INSTANT

24	RPSA03A1 82	M	12.00000		
----	-------------	---	----------	--	--

INLOC.TEAVA F.SUD.SAU SUD.LONG.PT.INST.ZN.IN COND.DISTR.AMPL.IN
CAN.PE PORT.PINA LA 10 M D = 1/2

25	4114000	BUCATA	21.00000		
----	---------	--------	----------	--	--

FITING PPR

26	RPSB23B1 82	M	12.00000		
----	-------------	---	----------	--	--

INLC.TV.PVC TIP U AP.MONT.IN NISA SUB PARDOS.SAU SUSP.PLANSEU
PE PORT.PINA LA 3 M D= 40 MM

27	RPSB25A1 82	BUCATA	9.00000		
----	-------------	--------	---------	--	--

INLOC.RAMIF.SIMPLA PVC-U DE 45;67,3;87,3 GRADE PT IMB.LIPIRE
RAMIF.CU D= 50 MM

L: 11433 -0001:6712813 -RAMIF.SIMPLA PVC-U 45 GRD 50- 50 NII 2167

28	RPEC02A2 82	BUCATA	9.00000		
----	-------------	--------	---------	--	--

INLOCUIRE LAMPA FLUORESCENTA

29	9910062	BUCATA	9.00000		
----	---------	--------	---------	--	--

LAMPA ILUMINAT CU LED ECHIVALENT 2X36W

30	RPEC01B 91	BUCATA	16.00000		
----	------------	--------	----------	--	--

CIRCUIT DE PRIZA EXEC.CU COND.DE AL SAU CU.IN TUBURDE
PROTECTIE LA CLADIRI ADMINISTRATIVE SI SOC.CUL

Nr.	Capitol lucrari	U/M	Cantitatea	Pretul unitar	Valoare
Crt.	Simbol			a)materiale	
	Denumire resursa			b)manopera	
	Observatii			c)utilaj	
	Corectii			d)transport	
	Liste Anexe			Total(a+b+c+d)	

31	9010201	BUCATA	14.00000		
----	---------	--------	----------	--	--

PRIZA DUBLA ST CP

32	5536248	BUCATA	2.00000		
----	---------	--------	---------	--	--

PRIZA MONOBLOC PT CU CP SIMB 161 250V 10-16A S3184

33	RPEE03F1 82	BUCATA	2.00000		
----	-------------	--------	---------	--	--

INLOC PRIZA 380V

34	RPEE02B1 82	BUCATA	1.00000		
----	-------------	--------	---------	--	--

INLOC COMUTATOR SERIE UNIP INGROPAT CONSTR IMPERMEABILA

L: 12011 -0001:5520366 -COMUTATOR CUMPARA ST.SIMBOL 0176 10 A ,250 V

35	CB14XB 91	MP	228.00000		
----	-----------	----	-----------	--	--

SCHELA METALICA TUBULARA PENTRU LUCRARI DE FINISAJE LA TAVANE PINA LA 7 M INALTIME

36	TRB05B22 82	TONE	1.00000		
----	-------------	------	---------	--	--

TRANSPORTUL MATERIALELOR PRIN PURTAT DIRECT,MATERIALE INCOMODE PESTE 25 KG DISTANTA 20M \$

PROIECTANT

Formular F3

Obiectiv: IMOBIL CH- CORP LABORATOARE

LISTA cu cantitatile de lucrari pe categorii de lucrari

Obiect: 01 REPARATII CURENTE LABORATOARE

Categorii: 02 HOL LABORATOR 35

					[ron]
Nr.	Capitol lucrari	U/M	Cantitatea	Pretul unitar	Valoare
Crt.	Simbol			a)materiale	
	Denumire resursa			b)manopera	
	Observatii			c)utilaj	
	Corectii			d)transport	
	Liste Anexe			Total(a+b+c+d)	

1	EA15B	99	M	9.00000	
---	-------	----	---	---------	--

SISTEM DE CANALETI-PLINTE, MONT.APARENT PE DIBLURI DIN
PVC,LATIMEA > 30 MM, DIN MATERIAL PLASTIC

L: EL01G -0009 6718226 -CANALET DIN MATERIAL PLASTIC, 50 X 100 MM

2	EI03A	99	BUCATA	18.00000	
---	-------	----	--------	----------	--

DIBLU DIN MATERIAL PLASTIC

L: EL18A -0071 6313356 -DIBLU CU EXPANDARE MARIMEA 10

3	RPCT10A1	82	MP	54.00000	
---	----------	----	----	----------	--

PREGATIREA PERETILOR PRIN SLEFUIRE IN VEDEREA ZUGRAVIRII

4	CF08C	02	MP	54.00000	
---	-------	----	----	----------	--

GLET DE IPSOS CU ADAOS ARACET 2 STR (GIPAC) APLIC MAN PE TENC
INT DRISC SAU SUPR ELEM DE BET

5	RPCR08A	09	MP	54.00000	
---	---------	----	----	----------	--

VOPSIREA,ZUGRAVELI LAVABILE,VOPSEA PA BAZA DE VINACET,LA INT-
EXT,2 STRATURI,TENCUIELI EXIST.

L: LC68G -M :2525124 -VAR LAVABIL PT INTERIOR

6	6113103		KG	14.00000	
---	---------	--	----	----------	--

AMORSA PENTRU VAR LAVABIL INTERIOR

Nr.	Capitol lucrari	U/M	Cantitatea	Pretul unitar	Valoare
Crt.	Simbol			a)materiale	
	Denumire resursa			b)manopera	
	Observatii			c)utilaj	
	Corectii			d)transport	
	Liste Anexe			Total(a+b+c+d)	

7	RPEC02A2	82	BUCATA	2.00000	
---	----------	----	--------	---------	--

INLOCUIRE LAMPA FLUORESCENTA

8	9910062		BUCATA	2.00000	
---	---------	--	--------	---------	--

LAMPA ILUMINAT CU LED ECHIVALENT 2X36W

9	CB14XB	91	MP	54.00000	
---	--------	----	----	----------	--

SCHELA METALICA TUBULARA PENTRU LUCRARI DE FINISAJE LA TAVANE PINA LA 7 M INALTIME

10	TRB05B22	82	TONE	1.00000	
----	----------	----	------	---------	--

TRANSPORTUL MATERIALELOR PRIN PURTAT DIRECT,MATERIALE INCOMODE PESTE 25 KG DISTANTA 20M \$

OFERTANT

Formular F3

Obiectiv: IMOBIL CH- CORP LABORATOARE

LISTA cu cantitatile de lucrari pe categorii de lucrari

Obiect: 01 REPARATII CURENTE LABORATOARE

Categorie: 03 LABORATOR 52

[ron]

Nr.	Capitol lucrari	U/M	Cantitatea	Pretul unitar	Valoare
Crt.	Simbol			a)materiale	
	Denumire resursa			b)manopera	
	Observatii			c)utilaj	
	Corectii			d)transport	
	Liste Anexe			Total(a+b+c+d)	

1	CMTA27A	02	BUCATA	36.00000	
---	---------	----	--------	----------	--

TAIERE CU DISC DE OTEL, TEAVA DE OTEL D. < 2"

TEAVA GAZ

2	RCSG10A	02	M	7.00000	
---	---------	----	---	---------	--

DEMONTARE CANALE DE VENTILATIE

3	RPCG30C	09	MP	21.70000	
---	---------	----	----	----------	--

PERETI DESPARTIT.PANOURI DIN GIPS-CARTON 1 STR PE FIECARE FATA,
PE STRUCT.MET.DIST.INTRE MONT. 30 CM

L: LC05G -0002:8558011 -SURUB MONTAJ AUTOFILETANT 35MM/1000 SUPERRAPID
L: LC27A -M :8527015 -PLACI GIPS-CARTON NORMALE GKB 12.5MM 1200/2000
L: LC49D -0003:8535042 -PROFIL DE CONTUR UW 100/0.6/4000 DIN OTEL GALVANIZAT
L: LC49E -0015:8535030 -PROFIL DE STRUCTURA CW 100/0.6/2750 DIN OTEL GALVANIZAT
L: LC74B -0004:8521060 -BANDA FIBRA DE STICLA PT ROSTURI LATIME=50MM-25M/ROLA

4	RPCT09C1	82	M CUB	0.80000	
---	----------	----	-------	---------	--

DEMOLAREA FUND PERETI TREPTE GRINZI SI STILPI CU MIJLOACE
MANUALE

5	RPCT10A1	82	MP	18.00000	
---	----------	----	----	----------	--

DESFACEREA TENCUIELILOR INTERIOARE SAU EXTERIOARE OBISNUITE
LA PERETI *

6	RPCJ09C1	82	MP	18.00000	
---	----------	----	----	----------	--

REP.TENC.LA PERETI BET.ARM.CU MORT.VAR CIM.100T PT.SPRIT SI
MORT.VAR CIM.10T PT.GRUND SI STRAT VIZ *

Nr.	Capitol lucrari	U/M	Cantitatea	Pretul unitar	Valoare
Crt.	Simbol			a)materiale	
	Denumire resursa			b)manopera	
	Observatii			c)utilaj	
	Corectii			d)transport	
	Liste Anexe			Total(a+b+c+d)	

7	RPCT10A1	82	MP	247.20000	
---	----------	----	----	-----------	--

PREGATIREA PERETILOR PRIN SLEFUIRE IN VEDEREA ZUGRAVIRII

8	CF08C	02	MP	247.20000	
---	-------	----	----	-----------	--

GLET DE IPSOS CU ADAOS ARACET 2 STR (GIPAC) APLIC MAN PE TENC
INT DRISC SAU SUPR ELEM DE BET

9	RCSD03A	02	MP	247.20000	
---	---------	----	----	-----------	--

PLASA FIBRA PENTRU ARMARE GLET

10	RPCR08A	09	MP	247.20000	
----	---------	----	----	-----------	--

VOPSIREA,ZUGRAVELI LAVABILE,VOPSEA PA BAZA DE VINACET,LA INT-
EXT,2 STRATURI,TENCUIELI EXIST.

L: LC68G -M :2525124 -VAR LAVABIL PT INTERIOR

11	6113103		KG	62.00000	
----	---------	--	----	----------	--

AMORSA PENTRU VAR LAVABIL INTERIOR

12	IZA05G1	82	MP	3.00000	
----	---------	----	----	---------	--

VOPSIT ANTICOROZ PE SUPRAF DE BETON TENCUIE CU VOPSEA
EPOXIDICA V 3207

VOPSITORII GLAFURI

13	RPCR49B1	82	MP	24.00000	
----	----------	----	----	----------	--

REVOPSIREA CORPURILOR DE RADIATOARE DE CALORIFER 1 STRAT
PESTE CEA VECHIE CU VOPS.PE BAZA DE ALCHID.*

14	RPCR31B1	82	MP	8.00000	
----	----------	----	----	---------	--

VOPSITORIE CU EMAIL ALCHIDAL PE TIMPLARIE DE LEMN LA INTERIOR SI
EXT.CU DOUA STRATURI *

baituire

Nr. Crt.	Capitol lucrari Simbol Denumire resursa Observatii Corectii Liste Anexe	U/M	Cantitatea	Pretul unitar a)materiale b)manopera c)utilaj d)transport Total(a+b+c+d)	Valoare
15	RCSH21A 02	MP	8.00000		
SLEFUIREA SI LACUIREA PANOURILOR SI USILOR DIN LEMN RASIN/FOIOASE/STEJAR					
16	RPCK02B1 82	MP	16.00000		
REPARARE FISURI PARDOSEALA					
17	RCSB22B 02	M	10.00000		
TAIEREA PLACILOR SAU ELEMENTELOR DIN BETON ARMAT, AVAND GROSIMEA DE PESTE 15CM					
18	RPCK44A 02	MP	75.20000		
STRAT SUPORT PT. PARDOSELI CU MORTAR AUTONIVELANT DE 3 - 15 MM					
19	RPCK12G 02	MP	75.20000		
REPARARE PARD.DIN MAT PLASTICE PE STR.SUP.EXISTENT					

L: LC62D -M :S-00132 -CORDON SUDURA PVC					
20	CL20A 02	BUCATA	1.00000		
GRILE DE VENTILATIE DIN PLASA SARMA 0,5X0,4M					

L: LC41J -0097:6306236 -GRILA VENTILATIE					
21	RPEC02A2 82	BUCATA	9.00000		
INLOCUIRE LAMPA FLUORESCENTA					
22	9910062	BUCATA	9.00000		
LAMPA ILUMINAT CU LED ECHIVALENT 2X36W					

Nr.	Capitol lucrari	U/M	Cantitatea	Pretul unitar	Valoare
Crt.	Simbol			a)materiale	
	Denumire resursa			b)manopera	
	Observatii			c)utilaj	
	Corectii			d)transport	
	Liste Anexe			Total(a+b+c+d)	

23	RPEC01B 91	BUCATA	20.00000		
----	------------	--------	----------	--	--

CIRCUIT DE PRIZA PRIN PARDOSEALA

24	9010201	BUCATA	20.00000		
----	---------	--------	----------	--	--

PRIZA DUBLA ST CP

25	RPEE03F1 82	BUCATA	2.00000		
----	-------------	--------	---------	--	--

INLOC PRIZA 380V

26	RPEE02B1 82	BUCATA	4.00000		
----	-------------	--------	---------	--	--

INLOC COMUTATOR SERIE UNIP INGROPAT CONSTR IMPERMEABILA

L: 12011 -0001:5520366 -COMUTATOR CUMPARA ST.SIMBOL 0176 10 A :250 V

27	CB14XB 91	MP	247.00000		
----	-----------	----	-----------	--	--

SCHELA METALICA TUBULARA PENTRU LUCRARI DE FINISAJE LA TAVANE PINA LA 7 M INALTIME

28	TRB05B22 82	TONE	2.00000		
----	-------------	------	---------	--	--

TRANSPORTUL MATERIALELOR PRIN PURTAT DIRECT,MATERIALE INCOMODE PESTE 25 KG DISTANTA 20M \$

OFERTANT

Formular F3

Obiectiv:IMOBIL CH- CORP LABORATOARE

LISTA cu cantitatile de lucrari pe categorii de lucrari

Obiect: 01 REPARATII CURENTE LABORATOARE

Categorie: 04 LABORATOR 132

[ron]

Nr.	Capitol lucrari	U/M	Cantitatea	Pretul unitar	Valoare
Crt.	Simbol			a)materiale	
	Denumire resursa			b)manopera	
	Observatii			c)utilaj	
	Corectii			d)transport	
	Liste Anexe			Total(a+b+c+d)	

1	CMTA27A	02	BUCATA	9.00000	
---	---------	----	--------	---------	--

TAIERE CU DISC DE OTEL, TEAVA DE OTEL D. < 2"

TEAVA GAZ

2	RCSG10A	02	M	12.00000	
---	---------	----	---	----------	--

DEMONTARE CANALE DE VENTILATIE

3	RPCT29A1	82	MP	90.00000	
---	----------	----	----	----------	--

DESFACERE PARDOSELI GRESIE

4	H1O02B	82	MP	90.00000	
---	--------	----	----	----------	--

CURATAREA MECANIZATA A SUPRAFETELOR DE BETON

5	RPCK02B1	82	MP	30.00000	
---	----------	----	----	----------	--

REPARARE STRAT SUPT PT.PARDOS.DIN MORTAR CIMENT MARCA 100-T DE 3CM GROS.CU FATA DRISCUITA FIN *

6	RPCK44A	02	MP	90.00000	
---	---------	----	----	----------	--

STRAT SUPT PT. PARDOSLI CU MORTAR AUTONIVELANT DE 3 - 15 MM

7	RPCK40A1	82	MP	90.00000	
---	----------	----	----	----------	--

PARDOSLI DIN PLACI DE GRESIE CERAMICA UNA CULOARE SI FORMA IN SUPRAFETE <60CMP/BUC.

L: 10139 -M :2419526 -GRESIE PORTELENETA ANTIDERAPANTA

Nr. Crt.	Capitol lucrari Simbol Denumire resursa Observatii Corectii Liste Anexe	U/M	Cantitatea	Pretul unitar a)materiale b)manopera c)utilaj d)transport Total(a+b+c+d)	Valoare
----------	--	-----	------------	---	---------

8	RPCH18G 09	MP		8.00000	
---	------------	----	--	---------	--

STRAT SUPTOR PENTRU FAIANTA DIN OSB

NISE+ MASA MICA

L: LRC48B -M :7801675 -PLACA OSB

9	RPCM14B1 82	MP		8.00000	
---	-------------	----	--	---------	--

PLACAJE FAIANTA NISE

L: 10138 -0015.2404535 -PLACI CESAROM GLAZUR.SIMP. ALB 100X100X 9 C. 1 S7813

10	RPCT10A1 82	MP		246.00000	
----	-------------	----	--	-----------	--

PREGATIREA PERETILOR PRIN SLEFUIRE IN VEDEREA ZUGRAVIRII

11	CF08C 02	MP		246.00000	
----	----------	----	--	-----------	--

GLET DE IPSOS CU ADAOS ARACET 2 STR (GIPAC) APLIC MAN PE TENC INT DRISC SAU SUPR ELEM DE BET

12	RPCR08A 09	MP		246.00000	
----	------------	----	--	-----------	--

VOPSIREA,ZUGRAVELI LAVABILE,VOPSEA PA BAZA DE VINACET,LA INT- EXT,2 STRATURI,TENCUIELI EXIST.

L: LC68G -M :2525124 -VAR LAVABIL PT INTERIOR

13	6113103	KG		61.50000	
----	---------	----	--	----------	--

AMORSA PENTRU VAR LAVABIL INTERIOR

14	RPIZA05G 99	MP		16.00000	
----	-------------	----	--	----------	--

VOPSIT.ANTICOROZ.LA CONFECTII METALICE

L: RIZ2A -0008:6107680 -EMAIL GRI PERCLORVINIL SR4070 NTR 54-75

15	RPCR49B1 82	MP		14.00000	
----	-------------	----	--	----------	--

REVOPSIREA CORPURILOR DE RADIATOARE DE CALORIFER 1 STRAT PESTE CEA VECHIE CU VOPS.PE BAZA DE ALCHID.*

Nr.	Capitol lucrari	U/M	Cantitatea	Pretul unitar	Valoare
Crt.	Simbol			a)materiale	
	Denumire resursa			b)manopera	
	Observatii			c)utilaj	
	Corectii			d)transport	
	Liste Anexe			Total(a+b+c+d)	
16	RPCR31B1 82	MP	20.00000		
VOPSITORIE CU EMAIL ALCHIDAL PE TIMPLARIE DE LEMN LA INTERIOR SI EXT.CU DOUA STRATURI *					
baituire					
17	RCSH21A 02	MP	20.00000		
SLEFUIREA SI LACUIREA PANOURILOR SI USILOR DIN LEMN RASIN/FOIOASE/STEJAR					
18	CL20A 02	BUCATA	2.00000		
GRILE DE VENTILATIE DIN PLASA SARMA 0,5X0,4M					
L: LC41J -0097 6306236 -GRILA VENTILATIE					
19	RPEC02A2 82	BUCATA	8.00000		
INLOCUIRE LAMPA FLUORESCENTA					
20	9910062	BUCATA	8.00000		
LAMPA ILUMINAT CU LED ECHIVALENT 2X36W					
21	RPEC01B 91	BUCATA	3.00000		
CIRCUIT DE PRIZA EXEC.CU COND.DE AL SAU CU.IN TUBURDE PROTECTIE LA CLADIRI ADMINISTRATIVE SI SOC.CUL					
22	9010201	BUCATA	9.00000		
PRIZA DUBLA ST CP					
23	5536248	BUCATA	3.00000		
PRIZA MONOBLOC PT CU CP SIMB 161 250V 10-16A S3184					

Nr. Crt.	Capitol lucrari Simbol Denumire resursa Observatii Corectii Liste Anexe	U/M	Cantitatea	Pretul unitar a)materiale b)manopera c)utilaj d)transport Total(a+b+c+d)	Valoare
24	RPEE02B1 82	BUCATA		4.00000	

INLOC COMUTATOR SERIE UNIP INGROPAT CONSTR IMPERMEABILA

L: 12011 -0001:5520366 -COMUTATOR CUMPARA ST.SIMBOL 0176 10 A ;250 V					
25	CB14XB 91	MP		246.00000	

SCHELA METALICA TUBULARA PENTRU LUCRARI DE FINISAJE LA TAVANE PINA LA 7 M INALTIME

26	RPSC16C1 82	BUCATA		3.00000	
----	-------------	--------	--	---------	--

INLOC.COMPL.LAV.FAIAN.PORT.SANIT.SEMIPORT.PE CONS.PE CARAM-BETON CU 2 ROB.SAU BAT.ST.TV.SC. PVC-U

L: 11402 -0001:2440474 -LAVOAR PORTELAN CU SPATAR LSD-400MM ALB C. 1 S1540					
L: 11405 -0005:4202797 -SIFON PT LAVOAR TIP BUTELIE ALAMA 1 1/4" S 9611					
L: 11413 -0014:4201339 -BATERIE AMEST. LAVOAR FONTA 1/2" EMAIL. JET PERL S8732					
27	7730406	BUCATA		1.00000	

INCALZITOR DE APA INSTANT

28	YC01 82	LEI	*****		
----	---------	-----	-------	--	--

TAXA SALUBRIS EVACUARE DESEURI GRESIE - 2 CONTAINERE X 750 LEI = 1500 LEI

29	TRB05B25 82	TONE		16.00000	
----	-------------	------	--	----------	--

TRANSPORTUL MATERIALELOR PRIN PURTAT DIRECT,MATERIALE INCOMODE PESTE 25 KG DISTANTA 50M \$

30	XA01 82	LEI	*****		
----	---------	-----	-------	--	--

DIFERENTE CHELTUIELI DE TRANSPORT \$

OFERTANT

Formular F3

Obiectiv: IMOBIL CH- CORP LABORATOARE

LISTA cu cantitatile de lucrari pe categorii de lucrari

Obiect: REPARATII CURENTE LABORATOARE

Categorie: 01 LABORATOR 158

[ron]

Nr.	Capitol lucrari	U/M	Cantitatea	Pretul unitar	Valoare
Crt.	Simbol			a)materiale	
	Denumire resursa			b)manopera	
	Observatii			c)utilaj	
	Corectii			d)transport	
	Liste Anexe			Total(a+b+c+d)	

1	CMTA27A 02	BUCATA	16.00000		
---	------------	--------	----------	--	--

TAIERE CU DISC DE OTEL, TEAVA DE OTEL D. < 2"

TEAVA GAZ

2	RPCH18G 09	MP	4.00000		
---	------------	----	---------	--	--

STRAT SUPORT PENTRU FAIANTA DIN OSB

L: LRC48B -M :7801675 -PLACA OSB

3	RPCM14B1 82	MP	4.00000		
---	-------------	----	---------	--	--

PLACAJE FAIANTA IN NISE

L: 10138 -0015:2404535 -PLACI CESAROM GLAZUR.SIMP. ALB 100X100X 9 C. 1 S7813

4	RPCT10A1 82	MP	340.20000		
---	-------------	----	-----------	--	--

PREGATIREA PERETILOR PRIN SLEFUIRE IN VEDEREA ZUGRAVIRII

5	CF08C 02	MP	340.20000		
---	----------	----	-----------	--	--

GLET DE IPSOS CU ADAOS ARACET 2 STR (GIPAC) APLIC MAN PE TENC
INT DRISC SAU SUPR ELEM DE BET

6	RPCR08A 09	MP	340.20000		
---	------------	----	-----------	--	--

VOPSIREA,ZUGRAVELI LAVABILE,VOPSEA PA BAZA DE VINACET,LA INT-
EXT,2 STRATURI,TENCUIELI EXIST.

L: LC68G -M :2525124 -VAR LAVABIL PT INTERIOR

Nr.	Capitol lucrari	U/M	Cantitatea	Pretul unitar	Valoare
Crt.	Simbol			a)materiale	
	Denumire resursa			b)manopera	
	Observatii			c)utilaj	
	Corectii			d)transport	
	Liste Anexe			Total(a+b+c+d)	

7	6113103	KG	85.00000		
---	---------	----	----------	--	--

AMORSA PENTRU VAR LAVABIL INTERIOR

8	IZA05G1 82	MP	6.00000		
---	------------	----	---------	--	--

VOPSIT ANTICOROZ PE SUPRAF DE BETON TENCUIE CU VOPSEA EPOXIDICA V 3207

VOPSITORII GLAFURI

9	RPIZA05G 99	MP	30.00000		
---	-------------	----	----------	--	--

VOPSIT.ANTICOROZ.LA CONFECTII METALICE

L: RIZ2A -0008-6107680 -EMAIL GRI PERCLORVINIL SR4070 NTR 54-75

10	RPCR49B1 82	MP	24.50000		
----	-------------	----	----------	--	--

REVOPSIREA CORPURILOR DE RADIATOARE DE CALORIFER 1 STRAT PESTE CEA VECHIE CU VOPS.PE BAZA DE ALCHID.*

11	RPCR31B1 82	MP	36.00000		
----	-------------	----	----------	--	--

VOPSITORIE CU EMAIL ALCHIDAL PE TIMPLARIE DE LEMN LA INTERIOR SI EXT.CU DOUA STRATURI *

baituire

12	RCSH21A 02	MP	8.00000		
----	------------	----	---------	--	--

SLEFUIREA SI LACUIREA PANOURILOR SI USILOR DIN LEMN RASIN/FOIOASE/STEJAR

13	RPCB22B 02	M	28.00000		
----	------------	---	----------	--	--

TAIEREA PLACILOR SAU A ELEMENTELOR DIN BETON

PENTRU RIGOLA

14	CR16B 02	M	14.00000		
----	----------	---	----------	--	--

RIGOLE DE SCURGERE

Nr. Crt.	Capitol lucrari	U/M	Cantitatea	Pretul unitar	Valoare
	Simbol			a)materiale	
	Denumire resursa			b)manopera	
	Observatii			c)utilaj	
	Corectii			d)transport	
	Liste Anexe			Total(a+b+c+d)	

15	SB43A1	82	BUCATA	2.00000	
----	--------	----	--------	---------	--

SIFON DE PARDOSEALA

16	RPCK02B1	82	MP	33.75000	
----	----------	----	----	----------	--

REPARARE FISURI PARDOSEALA

17	RPCK44A	02	MP	112.50000	
----	---------	----	----	-----------	--

STRAT SUPORT PT. PARDOSELI CU MORTAR AUTONIVELANT DE 3 - 15 MM

18	RPCK12G	02	MP	112.50000	
----	---------	----	----	-----------	--

REPARARE PARD.DIN MAT PLASTICE PE STR.SUP.EXISTENT

L: LC62D -M :S-00132 -CORDON SUDURA PVC

19	CD24B1	02	MP	15.20000	
----	--------	----	----	----------	--

PLACARE GHENA DE INSTALATII CU GIPSCARTON DISTANTA INTRE MONTANTI 0,6 M SI RF 60 GRD

20	CL20A	02	BUCATA	2.00000	
----	-------	----	--------	---------	--

GRILE DE VENTILATIE DIN PLASA SARMA 0,5X0,4M

L: LC41J -0097.6306236 -GRILA VENTILATIE

21	RPSC16C1	82	BUCATA	1.00000	
----	----------	----	--------	---------	--

INLOC.COMPL.LAV.FAIAN.PORT.SANIT.SEMI-PORT.PE CONS.PE CARAM-BETON CU 2 ROB.SAU BAT.ST.TV.SC. PVC-U

L: 11402 -0001:2440474 -LAVOAR PORTELAN CU SPATAR LSD-400MM ALB C. 1 S1540

L: 11405 -0005:4202797 -SIFON PT LAVOAR TIP BUTELIE ALAMA 1 1/4" S 9611

L: 11413 -0014:4201339 -BATERIE AMEST. LAVOAR FONTA 1/2" EMAIL JET PERL. S8732

22	RPSD01E1	82	BUCATA	2.00000	
----	----------	----	--------	---------	--

INLOC.ROB.SERV.CU RACORD 1/2 TOL

Nr. Crt.	Capitol lucrari	U/M	Cantitatea	Pretul unitar	Valoare
	Simbol			a)materiale	
	Denumire resursa			b)manopera	
	Observatii			c)utilaj	
	Corectii			d)transport	
	Liste Anexe			Total(a+b+c+d)	

23	7730406	BUCATA	1.00000		
----	---------	--------	---------	--	--

INCALZITOR DE APA INSTANT

24	RPSA03A1 82	M	12.00000		
----	-------------	---	----------	--	--

INLOC.TEAVA F.SUD.SAU SUD.LONG.PT.INST.ZN.IN COND.DISTR.AMPL.IN
CAN.PE PORT.PINA LA 10 M D = 1/2

25	4114000	BUCATA	21.00000		
----	---------	--------	----------	--	--

FITING PPR

26	RPSB23B1 82	M	32.00000		
----	-------------	---	----------	--	--

INLC.TV.PVC TIP U AP.MONT.IN NISA SUB PARDOS.SAU SUSP.PLANSEU
PE PORT.PINA LA 3 M D= 40 MM

27	RPSB25A1 82	BUCATA	9.00000		
----	-------------	--------	---------	--	--

INLOC.RAMIF.SIMPLA PVC-U DE 45;67,3;87,3 GRADE PT IMB.LIPIRE
RAMIF.CU D= 50 MM

L: 11433 -0001:6712813 -RAMIF.SIMPLA PVC-U 45 GRD 50- 50 NII 2167

28	RPEC02A2 82	BUCATA	15.00000		
----	-------------	--------	----------	--	--

INLOCUIRE LAMPA FLUORESCENTA

29	9910062	BUCATA	15.00000		
----	---------	--------	----------	--	--

LAMPA ILUMINAT CU LED ECHIVALENT 2X36W

30	EA15B 99	M	16.00000		
----	----------	---	----------	--	--

SISTEM DE CANALETI-PLINTE, MONT.APARENT PE DIBLURI DIN
PVC,LATIMEA > 30 MM, DIN MATERIAL PLASTIC

L: EL01G -0009:6718226 -CANALET DIN MATERIAL PLASTIC, 50 X 100 MM

Nr. Crt.	Capitol lucrari Simbol Denumire resursa Observatii Corectii Liste Anexe	U/M	Cantitatea	Pretul unitar a)materiale b)manopera c)utilaj d)transport Total(a+b+c+d)	Valoare
31	5536248	BUCATA	6.00000		
PRIZA MONOBLOC PT CU CP SIMB 161 250V 10-16A S3184					
32	RPEE03F1 82	BUCATA	2.00000		
INLOC PRIZA 380V					
33	RPEE02B1 82	BUCATA	1.00000		
INLOC COMUTATOR SERIE UNIP INGROPAT CONSTR IMPERMEABILA					
L: 12011 -0001:5520366 -COMUTATOR CUMPARA ST.SIMBOL 0176 10 A ,250 V					
34	CB14XB 91	MP	340.00000		
SCHELA METALICA TUBULARA PENTRU LUCRARI DE FINISAJE LA TAVANE PINA LA 7 M INALTIME					
35	TRB05B22 82	TONE	1.00000		
TRANSPORTUL MATERIALELOR PRIN PURTAT DIRECT,MATERIALE INCOMODE PESTE 25 KG DISTANTA 20M \$					
36	EF01A 99	BUCATA	2.00000		
TABLOU SIGURANTE					
L: EL20 -0014:731244D -CUTIE MASE PLASTICE CU 8 CIRCUITE,SIMBOL 0845					
37	VC01C1 82	BUCATA	2.00000		
VENTILATOR AXIAL NISA					
38	8000742	MP	15.00000		
PLACAJ LEMN					

Nr.	Capitol lucrari	U/M	Cantitatea	Pretul unitar	Valoare
Crt.	Simbol			a)materiale	
	Denumire resursa			b)manopera	
	Observatii			c)utilaj	
	Corectii			d)transport	
	Liste Anexe			Total(a+b+c+d)	
39	RPCM35A 02	MP			18.00000

PLACARE USI DULAPURI CU PANEL

L: LC05G -0001:8558010 -SURUB MONTAJ AUTOFILETANT 25MM/1000 SUPERRAPID

L: LC27B -M :N-00472 -PANEL FLAT 24MM ALB

Formular F3

Obiectiv: IMOBIL CH- CORP LABORATOARE

LISTA cu cantitatile de lucrari pe categorii de lucrari

Obiect: REPARATII CURENTE LABORATOARE

Categorie: 06 LABORATOR 249

					[ron]
Nr.	Capitol lucrari	U/M	Cantitatea	Pretul unitar	Valoare
Crt.	Simbol			a)materiale	
	Denumire resursa			b)manopera	
	Observatii			c)utilaj	
	Corectii			d)transport	
	Liste Anexe			Total(a+b+c+d)	

1	CMTA27A	02	BUCATA	12.00000	
---	---------	----	--------	----------	--

TAIERE CU DISC DE OTEL, TEAVA DE OTEL D. < 2"

TEAVA GAZ

2	RCSG10A	02	M	9.00000	
---	---------	----	---	---------	--

DEMONTARE CANALE DE VENTILATIE

3	RPCT29A1	82	MP	24.20000	
---	----------	----	----	----------	--

DESFACEREA PLACAJELOR FAIANTA

mese laborator + nise

4	RPCH18G	09	MP	24.20000	
---	---------	----	----	----------	--

STRAT SUPORT PENTRU FAIANTA DIN OSB

L: LRC48B -M :7801675 -PLACA OSB

5	RPCM35A	02	MP	18.00000	
---	---------	----	----	----------	--

PLACARE CU PLACI DIN PANEL ALB

L: LC05G -0001:8558010 -SURUB MONTAJ AUTOFILETANT 25MM/1000 SUPERRAPID

L: LC27B -M :N-00472 -PANEL FLAT 24MM ALB

6	RPCM14B1	82	MP	24.20000	
---	----------	----	----	----------	--

PLACAJE FAIANTA PE MESE SI NISE

L: 10138 -0015:2404535 -PLACI CESAROM GLAZUR.SIMP. ALB 100X100X 9 C. 1 S7813

Nr.	Capitol lucrari	U/M	Cantitatea	Pretul unitar	Valoare
Crt.	Simbol			a)materiale	
	Denumire resursa			b)manopera	
	Observatii			c)utilaj	
	Corectii			d)transport	
	Liste Anexe			Total(a+b+c+d)	
7	RPCT10A1 82	MP	281.30000		
PREGATIREA PERETILOR PRIN SLEFUIRE IN VEDEREA ZUGRAVIRII					
8	CF08C 02	MP	281.30000		
GLET DE IPSOS CU ADAOS ARACET 2 STR (GIPAC) APLIC MAN PE TENC INT DRISC SAU SUPR ELEM DE BET					
9	RPCR08A 09	MP	281.30000		
VOPSIREA,ZUGRAVELI LAVABILE,VOPSEA PA BAZA DE VINACET,LA INT-EXT,2 STRATURI,TENCUIELI EXIST.					
L: LC68G -M :2525124 -VAR LAVABIL PT INTERIOR					
10	6113103	KG	70.32000		
AMORSA PENTRU VAR LAVABIL INTERIOR					
11	IZA05G1 82	MP	6.00000		
VOPSIT ANTICOROZ PE SUPRAF DE BETON TENCUIE CU VOPSEA EPOXIDICA V 3207					
VOPSITORII GLAFURI					
12	RPIZA05G 99	MP	18.00000		
VOPSIT.ANTICOROZ.LA CONFECTII METALICE					
L: RIZ2A -0008:6107680 -EMAIL GRI PERCLORVINIL SR4070 NTR 54-75					
13	RPCR49B1 82	MP	14.50000		
REVOPSIREA CORPURILOR DE RADIATOARE DE CALORIFER 1 STRAT PESTE CEA VECHIE CU VOPS.PE BAZA DE ALCHID.*					
14	RPCR31B1 82	MP	36.00000		
VOPSITORIE CU EMAIL ALCHIDAL PE TIMPLARIE DE LEMN LA INTERIOR SI EXT.CU DOUA STRATURI *					
baituire					

Nr.	Capitol lucrari	U/M	Cantitatea	Pretul unitar	Valoare
Crt.	Simbol			a)materiale	
	Denumire resursa			b)manopera	
	Observatii			c)utilaj	
	Corectii			d)transport	
	Liste Anexe			Total(a+b+c+d)	

15	RPCNL-1	MP	3.36000		
----	---------	----	---------	--	--

REPARATII SI RECONDITIONARE USA DIN LEMN

16	RCSH21A 02	MP	36.00000		
----	------------	----	----------	--	--

SLEFUIREA SI LACUIREA PANOURILOR SI USILOR DIN LEMN RASIN/FOIOASE/STEJAR

17	RPCK02B1 82	MP	21.00000		
----	-------------	----	----------	--	--

REPARARE FISURI PARDOSEALA

18	RPCK44A 02	MP	90.00000		
----	------------	----	----------	--	--

STRAT SUPORT PT. PARDOSELI CU MORTAR AUTONIVELANT DE 3 - 15 MM

19	RPCK40A1 82	MP	90.00000		
----	-------------	----	----------	--	--

PARDOSELI DIN PLACI DE GRESIE CERAMICA UNA CULOARE SI FORMA IN SUPRAFETE <60CMP/BUC.

L: 10139 -M 2419526 -GRESIE PORTELENETA ANTIDERAPANTA

20	CL20A 02	BUCATA	2.00000		
----	----------	--------	---------	--	--

GRILE DE VENTILATIE DIN PLASA SARMA 0,5X0,4M

L: LC41J -0097:6306236 -GRILA VENTILATIE

21	RPSC16C1 82	BUCATA	2.00000		
----	-------------	--------	---------	--	--

INLOC.COMPL.LAV.FAIAN.PORT.SANIT.SEMIPT. PE CONS.PE CARAM- BETON CU 2 ROB.SAU BAT.ST.TV.SC. PVC-U

L: 11402 -0001:2440474 -LAVOAR PORTELAN CU SPATAR LSD-400MM ALB C. 1 S1540

L: 11405 -0005:4202797 -SIFON PT LAVOAR TIP BUTELIE ALAMA 1 1/4" S 9611

L: 11413 -0014:4201339 -BATERIE AMEST. LAVOAR FONTA 1/2" EMAIL. JET PERL S8732

22	RPSD01E1 82	BUCATA	2.00000		
----	-------------	--------	---------	--	--

INLOC.ROB.SERV.CU RACORD 1/2 TOL

Nr.	Capitol lucrari	U/M	Cantitatea	Pretul unitar	Valoare
Crt.	Simbol			a)materiale	
	Denumire resursa			b)manopera	
	Observatii			c)utilaj	
	Corectii			d)transport	
	Liste Anexe			Total(a+b+c+d)	
23	7730406	BUCATA	1.00000		
INCALZITOR DE APA INSTANT					
24	RPSA03A1 82	M	12.00000		
INLOC.TEAVA F.SUD.SAU SUD.LONG.PT.INST.ZN.IN COND.DISTR.AMPL.IN CAN.PE PORT.PINA LA 10 M D = 1/2					
25	4114000	BUCATA	21.00000		
FITING PPR					
26	RPSB23B1 82	M	12.00000		
INLC.TV.PVC TIP U AP.MONT.IN NISA SUB PARDOS.SAU SUSP.PLANSEU PE PORT.PINA LA 3 M D= 40 MM					
27	RPSB25A1 82	BUCATA	9.00000		
INLOC.RAMIF.SIMPLA PVC-U DE 45;67,3;87,3 GRADE PT IMB.LIPIRE RAMIF.CU D= 50 MM					
L: 11433 -0001:6712813 -RAMIF.SIMPLA PVC-U 45 GRD. 50- 50 NII 2167					
28	RPEC02A2 82	BUCATA	12.00000		
INLOCUIRE LAMPA FLUORESCENTA					
29	9910062	BUCATA	12.00000		
LAMPA ILUMINAT CU LED ECHIVALENT 2X36W					
30	RPEC01B 91	BUCATA	8.00000		
CIRCUIT DE PRIZA EXEC.CU COND.DE AL SAU CU.IN TUBURDE PROTECTIE LA CLADIRI ADMINISTRATIVE SI SOC.CUL					

Nr.	Capitol lucrari	U/M	Cantitatea	Pretul unitar	Valoare
Crt.	Simbol			a)materiale	
	Denumire resursa			b)manopera	
	Observatii			c)utilaj	
	Corectii			d)transport	
	Liste Anexe			Total(a+b+c+d)	

31	5536248	BUCATA	8.00000		
----	---------	--------	---------	--	--

PRIZA MONOBLOC PT CU CP SIMB 161 250V 10-16A S3184

32	RPEE03F1 82	BUCATA	2.00000		
----	-------------	--------	---------	--	--

INLOC PRIZA 380V

33	RPEE02B1 82	BUCATA	1.00000		
----	-------------	--------	---------	--	--

INLOC COMUTATOR SERIE UNIP INGROPAT CONSTR IMPERMEABILA

L: 12011 -0001:5520366 -COMUTATOR CUMPARA ST.SIMBOL 0176 10 A ;250 V

34	CB14XB 91	MP	281.30000		
----	-----------	----	-----------	--	--

SCHELA METALICA TUBULARA PENTRU LUCRARI DE FINISAJE LA TAVANE PINA LA 7 M INALTIME

35	TRB05B22 82	TONE	1.00000		
----	-------------	------	---------	--	--

TRANSPORTUL MATERIALELOR PRIN PURTAT DIRECT,MATERIALE INCOMODE PESTE 25 KG DISTANTA 20M \$

36	CD24B1 02	MP	15.20000		
----	-----------	----	----------	--	--

PLACARE GHENA DE INSTALATII CU GIPSCARTON DISTANTA INTRE MONTANTI 0,6 M SI RF 60 GRD

37	RPCM35A 02	MP	42.00000		
----	------------	----	----------	--	--

RAFTURI PANEL

L: LC05G -0001:8558010 -SURUB MONTAJ AUTOFILETANT 25MM/1000 SUPERRAPID

L: LC27B -M :N-00472 -PANEL FLAT 24MM ALB